



**PAMANTASAN NG LUNGSOD NG MAYNILA**  
(University of the City of Manila)  
Intramuros, Manila

**REQUEST FOR QUOTATION**

Date: \_\_\_\_\_  
RFP No.: 641119-181

Name of the Company: \_\_\_\_\_  
Address: \_\_\_\_\_  
Business Permit No.: \_\_\_\_\_  
TIN No.: \_\_\_\_\_  
PhilGEPS Reg. No.: \_\_\_\_\_

Please quote your best offer for the item/s described below, subject to the Terms and Conditions provided at the back portion of this request for quotation. Submit your quotation duly signed by you or your duly authorized representative not later than \_\_\_\_\_.

Open quotations may be submitted, manually or through facsimile or email at the address and contact number indicated below.

\_\_\_\_\_  
ATTY. MAY ANGELI M. ESTOLAS  
Acting Chief, Procurement Office


After having carefully read and accepted the Terms and Conditions, I/We submit our quotation/s for the item/s as follows:

as follows:

Item Description		QTY	Approved Budget for the Contract (ABC)	OFFER					
				Price			Compliance with Technical Specifications (please check)		Remarks
							Yes	No	
QTY	Unit Price	Total Price	Yes	No					
Supply and Installation of Metal Cladding Including Bracing/bracket of column post for Steel Louver with Paint Finish at Gusaling Bagatsing – Re-Canvass									
Lot I	Supply and Installation of Metal Cladding Including Bracing/bracket of column post for Steel Louver with Paint Finish at Gusaling Bagatsing		598,016.98						
I.	<u>Scope of Work:</u> Consists of furnishing of all materials, labor, tools, equipment and other incidentals necessary for the satisfactory completion of the works as indicated on the plans and in accordance with the specifications and as here in specified: <div><div>1.</div><div>Supply, Delivery, Hoisting and installation of steel louver.</div><div>2.</div><div>Supply, fabrication and installation of bracing/bracket column posts for the steel louver including paint finish.</div></div>								

	3. Clearing of area after completion of works. No. of days to complete the project: 60 C.D.								
II.	<b>Materials:</b>								
1	Steel louver using 1.5mm x 2 x 3 rectangular tube and 1.0mm galvanize steel sheet Z profile bending and ¾" Flat bar strips to cover welded louvers, Rust Proofing and Paint Fin	111 Sq.Mts.							
2	¼" x 2" x 2" x 20", Angular Bar	14 pcs							
3	10mm x 4-1/2", m Stainless Bolts & Nuts Washer	170 pcs							
4	3/8" Expansion Bolt	120 pcs							
5	Welding rod 3.2mm E6013	1 box							
6	3/8" Masonry Drill bit	6 pcs							
7	1/8" Metal Drill Bit	5 pcs							
8	3/8" Metal Drill Bit	6 pcs							
9	Red Oxide paint	4 gal							
10	QDE (Verify Color)	4 gal							
11	Paint Thinner	2 gal							
12	Paint Brush 2'	12 pcs							
13	Baby Roller	12 pcs							
14	Sand Paper	25 pcs							
15	Estopa round Small	1 kl							
	<b><u>Eligibility Requirements:</u></b> 1. Updated Mayor's Permit/Business Permit 2. Income/Business Tax Return 3. PCAB License 4. PhilGEPS Registration Number 5. Omnibus Sworn Statement								
	<b>PR # 02-19-06</b>								
	<b>Total Amount, PHP</b>		<b>598,016.98</b>						
	<b>Terms of Payment:</b>								
	<b>Delivery Period:</b>								

This is to certify that I personally conducted the canvass and that the data herein are true and correct.

  
**LORENZO S. DE VERA**  
Canvasser

\_\_\_\_\_  
(Signature over Printed Name)

Landline: \_\_\_\_\_  
Mobile No.: \_\_\_\_\_  
E-Mail: \_\_\_\_\_